



**MATERIAL LIST**

ITEM	QTY.	DESCRIPTION
①	1	TAPPED & THREADED D.I. CAP, MJ. x FIP
②	2	2" GALVANIZED PIPE, LENGTH TO FIT.
③	1	2" 90° GALVANIZED ELBOW, FIPxFIP.
④	1	2" BALL VALVE, FIPxFIP. (OPTIONAL GATE VALVE)
⑤	1	TRAFFIC RATED BOX AND COVER, OR EQUAL

**NOTES:**

1. NUMBER AND LOCATION OF THE TEMPORARY BLOW-OFFS WILL BE AS SHOWN ON THE DESIGN PLANS OR AS DIRECTED BY THE DISTRICT IN THE FIELD.
2. PROVIDE TEMPORARY BLOCKING FOR BLOW-OFFS TO RESIST TEST PRESSURES.

**TEMPORARY BLOW-OFF ASSEMBLY  
FOR NEW WATERMAIN**

NOT TO SCALE

Detail Approvals  
 Engineer GSM  
 Manager DPK

**NORTHSHORE UTILITY DISTRICT  
STANDARD WATER DETAILS**

17