



MATERIAL LIST		
ITEM	QTY.	DESCRIPTION
①	1	TAPPED & THREADED D.I. CAP, M.J. x FIP
②	2	2" GALVANIZED PIPE, LENGTH TO FIT.
③	1	2" 90° GALVANIZED ELBOW, FIPxFIP.
④	1	2" BALL VALVE, FIPxFIP. (OPTIONAL GATE VALVE)
⑤	1	TRAFFIC RATED BOX AND COVER, OR EQUAL

NOTES:

1. NUMBER AND LOCATION OF THE TEMPORARY BLOW-OFFS WILL BE AS SHOWN ON THE DESIGN PLANS OR AS DIRECTED BY THE DISTRICT IN THE FIELD.
2. PROVIDE TEMPORARY BLOCKING FOR BLOW-OFFS TO RESIST TEST PRESSURES.

TEMPORARY BLOW-OFF ASSEMBLY FOR NEW WATERMAIN

NOT TO SCALE

Detail Approvals
 Engineer GSM
 Manager DPK

NORTHSHORE UTILITY DISTRICT STANDARD WATER DETAILS

17

June 2015
W-17(2InchTempBO).dwg